COMPILED EASEMENT PLAN SCHEDULE				
PART	LOT	REG'D. PLAN	PIN	PERPENDICULAR WIDTH
1	8	49M-**	Pt. 57368-0057 (LT)	10.00
3	9			7.00
4	10			7.00
5	11			7.00
6	32			7.00
7	12			7.00
8	13			7.00
9	14			7.00
10	15			7.00
11	16			7.00
12	17			7.00
13	18			7.00
14	19			7.00
15				7.00
17	22			7.00
18	19			7.00
19	20			7.00
20	24			7.00
21	26			7.00
24				7.00
25				7.00
27				7.00
28	29			7.00

PLAN OF SURVEY SCHEDULE			
PART	LOT/BLK	REG'D. PLAN	PIN
2	Block 34	49M-**	Pt. 57368-0057 (LT)
16	20		
22	26		
23	27		
26	28		



PLAN 49R – _____

RECEIVED AND DEPOSITED

_____
(date)

_____
Representative for LAND REGISTRAR FOR THE LAND TITLES DIVISION OF RENFREW (No. 49)

I REQUIRE THIS PLAN TO BE DEPOSITED UNDER THE LAND TITLES ACT

DATE: DECEMBER 18, 2014

_____
ADAM KASPRZAK

COMPILED EASEMENT PLAN
OF
LOTS 8 to 20, INCLUSIVE
AND OF
LOTS 22, 24, 26, 29 & 32
AND
PLAN OF SURVEY
OF PART OF
LOTS 20, 26 & 27
AND PART OF
BLOCK 34
REGISTERED PLAN 49M – ****
TOWNSHIP OF GREATER MADAWASKA
COUNTY OF RENFREW

SCALE 1 : 1500

15 0 30 60 90 120 150 METRES

ADAM KASPRZAK SURVEYING LTD.

BEARING NOTE:
BEARINGS ARE UTM GRID AND ARE REFERRED TO THE WESTERLY LIMIT OF LOT 26, AS SHOWN ON REGISTERED PLAN 49M-**, HAVING A BEARING OF N20°49'20"W AND ARE REFERRED TO THE CENTRAL MERIDIAN OF UTM ZONE 18, 75° WEST.

ASTRONOMIC BEARINGS CAN BE CALCULATED BY ROTATING THE GRID BEARINGS COUNTER CLOCKWISE 1°15'20" AS REFERRED TO PLAN 49R-8760.

DISTANCE NOTE:
DISTANCES AND COORDINATES SHOWN ON THIS PLAN ARE IN METRES AND CAN BE CONVERTED TO FEET BY DIVIDING BY 0.3048.

DISTANCE NOTE:
DISTANCES SHOWN ON THIS PLAN ARE GROUND DISTANCES AND CAN BE CONVERTED TO GRID DISTANCES BY MULTIPLYING BY A COMBINED SCALE FACTOR OF 0.9998.

NOTE:
SSIB PLANTED DUE TO INSUFFICIENT OVERBURDEN.

INTEGRATION DATA:

COORDINATES ARE DERIVED FROM INFORMATION CONTAINED ON PLAN 49R-18433, WHICH USED PRECISE POINT POSITIONING (PPP) SERVICE AND ARE REFERRED TO UTM ZONE 18 (75° WEST) NAD83 (CSRS) (1997).

POINT ID	NORTHING	EASTING
ORP1	5 011 974.805	361 548.209
ORP2	5 011 763.867	361 628.440

COORDINATE VALUES ARE TO RURAL ACCURACY PER SEC. 14 (2) OF O. REG. 216/10 AND CANNOT, IN THEMSELVES, BE USED TO RE-ESTABLISH CORNERS OR BOUNDARIES SHOWN ON THIS PLAN.

NOTE:

1. ALL PARTS LIE WHOLLY WITHIN THE LIMITS OF THE LOTS AS SHOWN.
2. ALL PARTS HAVE A PERPENDICULAR WIDTH OF 6.00 METRE, 7.00 METRES OR 10.00 METRES AS SHOWN ON THE PLAN.



3. ALL PREVIOUSLY UNDEFINED LIMITS ARE PARALLEL WITH EXISTING LIMITS AND ARE PRODUCTIONS THEREOF AND INTERSECT AT COMMON POINTS, UNLESS OTHERWISE NOTED.

LEGEND (If Applicable)

IB	– IRON BAR
SIB	– STANDARD IRON BAR
SSIB	– SHORT STANDARD IRON BAR
■	– MONUMENT FOUND
□	– MONUMENT SET
CP	– CONCRETE PIN
WIT	– WITNESS
RB	– ROCK BAR
(OU)	– ORIGIN UNKNOWN
(MEAS)	– MEASURED
(ORP)	– OBSERVED REFERENCE POINT
(918)	– GIBSON, SURY & ROWE LTD.
(1557)	– SURY, ROWE & KASPRZAK LTD.
(AK)	– ADAM KASPRZAK SURVEYING LTD.
(OH)	– ONTARIO HYDRO
(P1)	– REGISTERED PLAN 49M-**

SURVEYOR'S CERTIFICATE

I CERTIFY THAT:
1. THIS SURVEY AND PLAN ARE CORRECT AND IN ACCORDANCE WITH THE SURVEYS ACT, THE SURVEYORS ACT, THE LAND TITLES ACT AND THE REGULATIONS MADE UNDER THEM.
2. THE SURVEY WAS COMPLETED ON DECEMBER 12th, 2014.

DATE: DECEMBER 18, 2014

_____
ADAM KASPRZAK
ONTARIO LAND SURVEYOR

ADAM KASPRZAK SURVEYING LTD.
ONTARIO LAND SURVEYORS
113 ARGYLE ST. S., P.O. BOX 633
RENFREW ONTARIO K7V 4E7
PHONE (613) 432-3048

SCALE: 1 : 1500 | REF: 14-2042-EASEMENT-D
FILE No :